Town of Hopedale, MA Park Commission



Presented by: Daniel Ciaramicoli, PE



PRESENTATION AGENDA

- 1. Introduction
- 2. Project Overview
- 3. Wall Evaluation
- 4. Subsurface Investigation
- 5. Replacement Alternatives
- 6. Discussion



PROJECT OVERVIEW

- **1.** Wall Evaluation (Completed September 2023)
 - Inspect the existing wall and quantify deficiencies
- 2. Subsurface Exploration (Completed September 2023)
 - Assess soil properties for wall foundation design
- **3.** Alternatives Analysis (Completed November 2023)
 - Review solutions and choose a Preferred Alternative
- 4. Preliminary Design (Estimated Completion February 2024)
 - Initial design and layout of the Preferred Alternative
- 5. Final Design (Estimated Completion May 2024)
 - Initial design and layout of the Preferred Alternative



WALL EVALUATION



STA 0+00 TO 2+20





STA 2+20 TO 2+80



STA 2+80 TO 4+30





STA 4+30 TO 7+40



STA 9+60 TO 10+15





STA 10+15 TO 10+60





STA 10+60 TO 11+60





STA 11+60 TO 12+10






STA 12+10 TO 13+10





SUBSURFACE INVESTIGATION





ALTERNATIVE 1 – DO NOTHING

- 1. Continued deterioration of the wall and eventual collapse of compromised areas.
 - Outcome of a wall collapse would be unfavorable due to proximity of abutters, public sidewalks / roadways and utilities





ALTERNATIVE 2 – DISMANTLE AND RESTACK

Remove and restack the existing wall. Supplement with additional stone as needed.

- Estimated Cost: \$1,630,000
- Estimated Construction Schedule: 4 Months
- Impacts During Construction
 - Temporary Shoring needed at 25 Northrop Street
 - Lane closures on Northrop Street and Freedom Street
- Wall would look similar to existing wall






ALTERNATIVE 3A – IN-PLACE CONCRETE BLOCK WALL

Remove the existing wall and replace with a modular concrete block wall in the same position.


- Estimated Cost: \$1,120,000
- Estimated Construction Schedule: 3 Months
- Impacts During Construction
 - Temporary shoring needed at 25 Northrop Street
 - Lane closures on Northrop Street and Freedom Street
- Concrete block with pattern instead of real stone





ALTERNATIVE 3B – IN-FRONT CONCRETE BLOCK WALL


- Build a new modular concrete block wall in front of the existing stone wall
 - Estimated Cost: \$650,000
 - Estimated Construction Schedule: 2.5 Months
 - Impacts During Construction
 - Closure of sidewalk along
 Freedom Street
 - Security fence at 25 Northrop Street
 - Concrete block with pattern instead of real stone



ALTERNATIVE 4A – IN-PLACE C.I.P CONCRETE WALL WITH STONE FACADE

Remove the existing stone wall and build a new cast-in-place concrete wall in its place. Add an aesthetic stone façade.


- Estimated Cost: \$ 1,880,000
- Estimated Construction Schedule: 4 to 5 Months
- Impacts During Construction
 - Temporary shoring needed at 25 Northrop Street
 - Lane closures on Northrop Street and Freedom Street
- Stone façade similar in appearance to the existing wall.






ALTERNATIVE 4B – IN-FRONT C.I.P CONCRETE WALL WITH STONE FACADE

- Build a new cast in place concrete wall in front of the existing stone wall. Add an aesthetic stone façade.
- Estimated Cost: \$ 1,530,000
- Estimated Construction Schedule:
 3.5 Months
- Impacts During Construction
 - Closure of sidewalk along Freedom Street
 - Security fence at 25 Northrop Street
- Stone façade similar in appearance to the existing wall.







THANK YOU!

QUESTIONS & DISCUSSION